


SECTION A-A
No Scale



NOTE:

1. Use #4 (1/2") rebar slab reinforcement in r.o.w placed @ 6" from each edge. rebar to be 2' on center, being 6" on center in the gutter.
2. Contraction joints shall be 1/3 the depth of the slab.
3. Maximum pavement slope allowed within 30' of the street is 4.5%.
4. Aggregate used in the concrete mix shall be granite.
5. If water shutoff is in the driveway pavement a cover as manufactured by Mcdonald 74M1A series with a 8" opening frame & cover or equal shall be installed.
6. Highback curb must be poured monolithically with driveway, surmountable curb may be poured separately.



**CITY OF
CHANHASSEN**

COMMERCIAL/INDUSTRIAL
CONCRETE DRIVEWAY APRON

REVISED: 1-20

FILE NAME: G:\ENG\SPECS\5207

ENGINEERING DEPARTMENT

PLATE NO.:

5207